


- 2. FLEECE-BACKING MUST BE REMOVED FROM THE MEMBRANE SO THAT WATER CUT-OFF MASTIC IS IN DIRECT CONTACT.
- 3. THE HOLE IN THE MEMBRANE SHALL EXCEED THE DIAMETER OF THE DRAIN PIPE, BUT SHALL BE NO LESS THAN 1/2" (13mm) FROM THE ATTACHMENT POINTS OF THE DRAIN CLAMPING RING.
- 4. ALL BOLTS OR CLAMPS MUST BE IN PLACE TO PROVIDE CONSTANT COMPRESSION ON WATER CUT-OFF MASTIC.
- 5. ROOF DRAIN SIZE AND NUMBER OF DRAINS SHALL BE IN ACCORDANCE WITH THE LOCAL CODES.





- → FleeceBACK MEMBRANE
- → FLEX FAST/AQUABASE
- → APPROVED SUBSTRATE

→SEE NOTE(S)

ROOF DRAIN WITH CONTINUOUS MEMBRANE

For additional information, refer to Specifications



igotimes2020 Carlisle SynTec a division of Carlisle Construction Materials Incorporated